

COMMERCIAL RECYCLING **EQUIPMENT**

MOBILE COMPACTOR MC32WBL

THE BENEFITS

- Safe & easy to operate
- Cuts uplifts & transport costs
- It has a 3/4 full & full indicator
- Liquid retentive

- Saves space (Up to 6:1 compaction ratio)
- Odour free, tidier & more efficient site
- Can be loaded while running
- Pendulum Packer insures ram and hoses are kept away



Visit www.pearce-group.co.uk or call us on **0800 083 3333**



TECHNICAL DATA MOBILE COMPACTOR MC32WBL

Dimensional Data

Overall Width	2400mm
Overall Length	7500mm
Overall Height	2600mm
Machine Weight	5800kg
Machine Capacity	22m²

Electrical Specification

Supply Voltage	415vac
Phase	3ph
Max Current	32A
IP Rating	IP55
Control Circuit	24vdc

Machine Specification

Compaction Force	38 tonnes
Motor	5.5kw
System Pressure	230 bar
Cycle Time	45 secs
75% Full Light	
100% Full Light	

Optional Features


SmartTec (status notifications)
SolarPac (solar power)
Various Hopper Configurations






Having this Compactor means we don't have lots of bins dotted around the site anymore with rubbish lying around, really helping to keep our site nice & tidy. Being right in the middle of the public domain it's very important for us to keep smells & rubbish at a minimum which the Compactor does really well. It's also reduced the amount of vehicles having to come on site & helped to create savings. Our service is also twice a year, which is always on time, running nice & smoothly.

Colin Hendon Gascoyne Cecil







GET IN TOUCH



Pearce Group Head Office
Pearce House, Acrewood Way,
St Albans, Hertfordshire, AL4 0JY

Email: compaction@pearce-recycling.co.uk

Web: www.pearce-group.co.uk

Call: **0800 083 3333**

